



NOTES:

1. ALL EXISTING FOOTPATHS AND CONCRETE KERBS AND CHANNELS TO BE SAWCUT OR BROKEN OUT TO NEAREST JOINT OUTSIDE THE LIMITS OF THE CROSSING.
2. CONCRETE STRENGTH TO BE 25MPA AFTER 28 DAYS
3. FOR INDUSTRIAL AREAS USE 150MM TO 200MM CONCRETE THICKNESS
4. CHARCOAL COLOURING TO BE ADDED AT 4% UNLESS STATED OTHERWISE