



NOTES:

1. 125mm Concrete Pavement to be 25MOa at 28 days.
2. Footpath crossfall top match existing.
3. Crossing to be excavated to firm base as approved by Council Superintendent. Over excavation is to be reinstated with approved material such as rock or packing sand to form a level base.
4. Bluestone base to be 100mm depth of 20 MPa concrete.
5. Joints to be filled with grey mortar 20mm thick
6. Concrete to be laid flush with Pitchers within crossover